

Addendum #2
Project #2694
Fox River State Trail Construction
Parks
November 7, 2024
Request for Bid

See original specification packet for addresses

THIS ADDENDUM IS ISSUED TO MODIFY, EXPLAIN OR CORRECT THE ORIGINAL DRAWINGS AND SPECIFICATIONS AND IS HEREBY MADE PART OF THE CONTRACT DOCUMENTS. THIS ADDENDUM MUST BE ACKNOWLEDGED ON THE ADDENDUM RECEIPT SCHEDULE, WHICH WAS INCLUDED IN THE ORIGINAL DOCUMENT PACKAGE.

Vendors are required to read entire addendum to determine requirements affecting their contract.

Addendum #2

This addendum is for the following:

- To update project specs
- To provide information for the bid opening

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Archaeological monitoring commitments added.

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
27	Miscellaneous quantity sheet modified for bid item 602.0410

Special Provisions

4. Prosecution and Progress

Add the following:

- Any work beyond shoulder slope/ditch within the boundaries of the human burial site shall be monitored by a qualified archaeologist.
 - The monitor has been assigned to UW-M
 - Please provide Matt Kries, matt.kriese@browncountywi.gov with an approximate date of need/proposed construction start schedule.
 - Please notify BTS/CR (Lynn Cloud 608-266-0099 or lynn.cloud@dot.wi.gov) a minimum of two weeks prior to the date of need.
 - Please send the Pre-construction meeting notice to the assigned archaeologist Nicholas Weber, njweber@uwm.edu
- The burial site should not be used for borrow or waste disposal, or for the staging of personnel, equipment and/or supplies.

Bid Opening Information:

Microsoft Teams [Need help?](#)

[Join the meeting now](#)

Meeting ID: 215 169 553 458

Passcode: XGLeYa

Dial in by phone

872-256-4158 United States, Chicago

Phone conference ID: 808 909 271#

Bid opening will start at 11:00am. It is recommended to log into the meeting at least 5 minutes prior to start. Bid prices will be read aloud twice for each vendor submitting a bid.

Reminder: All bids must either be mailed, or hand delivered and received by 11:00am CST on Thursday, November 14, 2024. Hand delivered or mailed bids are go to the County Clerk, 305 E Walnut Street, Room 120, Green Bay, WI 54301. Bids received after 11:00am will not be opened.

BID DUE DATE

11/14/24 BY 11:00 A.M. CST

CURB AND GUTTER ITEMS

CATEGORY	STA	OFFSET	TO	STA	OFFSET	204.0110 REMOVING ASPHALTIC SURFACE SY	204.0150 REMOVING CURB & GUTTER LF	465.0105 ASPHALTIC SURFACE TON	SPV.0090.01 CONCRETE CURB & GUTTER 24-INCH LF	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER LF	690.0150* SAWING ASPHALT LF	690.0250* SAWING CONCRETE LF
0010	90+77	9.9' RT	-	91+05	10.9' LT	10	39	3	39	39	48	4
0010	91+29	10.8' LT	-	91+53	9.7' RT	9	36	3	36	36	46	4
0010	94+94	9.9' RT	-	95+15	10.4' LT	8	31	3	31	31	38	4
0010	95+52	12.9' LT	-	95+53	14.2' RT	7	27	2	27	27	31	4
0010	146+04	18.6' RT	-	146+04	15.1' LT	8	34	3	34	34	38	4
0010	146+28	22.9' RT	-	146+28	21.8' LT	10	45	3	45	45	49	4
0010	212+41	23.9' LT	-	212+50	22.4' RT	11	47	4	47	47	51	4
0010	212+65	11.8' LT	-	212+71	18.6' RT	7	31	2	31	31	35	4
TOTAL						70	290	23	290	290	336	32

REMOVING PAVEMENT

CATEGORY	STA	TO	STA	LOCATION	204.0155 REMOVING CONCRETE SIDEWALK SY
0010	9+68	-	323+80	MAINLINE	32
TOTALS					32

*ADDITIONAL QUANTITIES LISTED ELSEWHERE

EXCAVATION COMMON

CATEGORY	STA	TO	STA	LOCATION	205.0100 EXCAVATION COMMON CY
0010	9+68	-	323+80	MAINLINE	3,432
TOTALS					3,432

BASE AGGREGATE

CATEGORY	STA	TO	STA	305.0110 BASE AGGREGATE DENSE 3/4-INCH TON	624.0100 WATER MGAL
0010	9+68	-	323+80	800	8
TOTALS				800	8

HMA PAVEMENT

CATEGORY	STA	TO	STA	460.5224 HMA PAVEMENT 4 LT 58-28 S TON
0010	9+68	-	323+80	7,230
TOTAL				7,230

CONCRETE CURB RAMP ITEMS

CATEGORY	STA	TO	STA	LOCATION	602.0410 CONCRETE SIDEWALK 5-INCH SY	602.0505 CURB RAMP DETECTABLE WARNING FIELD YELLOW SF	650.9000 CONSTRUCTION STAKING CURB RAMPS EACH
0010	9+68	-	9+76	MAINLINE	98	24	1
0010	10+23	-	10+31	MAINLINE	98	24	1
0010	52+02	-	52+12	MAINLINE	117	24	1
0010	52+44	-	52+56	MAINLINE	146	24	1
0010	61+02	-	61+09	MAINLINE	84	24	1
0010	61+50	-	61+63	MAINLINE	181	24	1
0010	90+82	-	91+03	MAINLINE	386	42	1
0010	91+30	-	91+48	MAINLINE	205	42	1
0010	94+91	-	95+13	MAINLINE	278	39	1
0010	95+53	-	95+60	MAINLINE	84	24	1
0010	145+96	-	146+03	MAINLINE	85	24	1
0010	146+29	-	146+36	MAINLINE	279	24	1
0010	212+36	-	212+45	MAINLINE	99	24	1
0010	212+68	-	212+76	MAINLINE	98	24	1
0010	301+77	-	301+84	MAINLINE	84	24	1
0010	302+12	-	302+19	MAINLINE	85	24	1
TOTALS					2407	435	16


RESTORATION ITEMS

CATEGORY	LOCATION	625.0100 TOPSOIL SY	628.2006 EROSION MAT URBAN CLASS I TYPE A SY	629.0205 FERTILIZER TYPE A CWT	630.0140 SEEDING MIXTURE NO. LB	630.0500 SEED WATER MGAL
0010	MAINLINE	75	75	10	2	1
TOTALS		75	75	10	2	1

SCHEDULE OF PRICES

Bidder MUST fill in "Schedule of Prices" for all items of work below; failure to do so will invalidate your quotation.

ITEM NUMBER	DESCRIPTION	QTY.	UNIT	UNIT BID PRICE	AMOUNT BID
204.0110	Removing Asphaltic Surface	70	SY	\$	\$
204.0150	Removing Curb & Gutter	290	LF	\$	\$
204.0155	Removing Concrete Sidewalk	32	SY	\$	\$
205.0100	Excavation Common	3432	CY	\$	\$
213.0100	Finishing Roadway (project) 01. 4987-13-71	1	EACH	\$	\$
305.0110	Base Aggregate Dense 3/4-Inch	800	TON	\$	\$
460.5224	HMA Pavement 4 LT 58-28 S	7230	TON	\$	\$
465.0105	Asphaltic Surface	23	TON	\$	\$
602.0410	Concrete Sidewalk 5-Inch	2407	SY	\$	\$
602.0505	Curb Ramp Detectable Warning Field Yellow	435	SF	\$	\$
619.1000	Mobilization	1	EACH	\$	\$
624.0100	Water	8	MGAL	\$	\$
625.0100	Topsoil	75	SY	\$	\$
628.1504	Silt Fence	11855	LF	\$	\$
628.1520	Silt Fence Maintenance	11855	LF	\$	\$
628.1905	Mobilizations Erosion Control	1	EACH	\$	\$
628.1910	Mobilizations Emergency Erosion Control	2	EACH	\$	\$
628.2006	Erosion Mat Urban Class I Type A	75	SY	\$	\$
628.7015	Inlet Protection Type C	10	EACH	\$	\$
628.7555	Culvert Pipe Check	85	EACH	\$	\$
628.7570	Rock Bags	20	EACH	\$	\$
629.0205	Fertilizer Type A	10	CWT	\$	\$
630.0140	Seeding Mixture No. 40	2	LB	\$	\$
630.0500	Seed Water	1	MGAL	\$	\$
643.0300	Traffic Control Drums	1440	DAY	\$	\$
643.0420	Traffic Control Barricades Type III	180	DAY	\$	\$
643.0715	Traffic Control Warning Lights Type C	1440	DAY	\$	\$
643.0900	Traffic Control Signs	1044	DAY	\$	\$
643.1070	Traffic Control Cones 42-Inch	1440	DAY	\$	\$
643.5000	Traffic Control	1	EACH	\$	\$
644.1810	Temporary Pedestrian Barricade	384	LF	\$	\$
646.1020	Marking Line Epoxy 4-Inch	7742	LF	\$	\$
646.6020	Marking Stop Line Epoxy 12-Inch	108	LF	\$	\$



ITEM NUMBER	DESCRIPTION	QTY.	UNIT	UNIT BID PRICE	AMOUNT BID
650.5000	Construction Staking Base	31412	LF	\$	\$
650.5500	Construction Staking Curb Gutter and Curb & Gutter	290	LF	\$	\$
650.8000	Construction Staking Resurfacing Reference	31412	LF	\$	\$
650.9000	Construction Staking Curb Ramps	16	EACH	\$	\$
690.0150	Sawing Asphalt	570	LF	\$	\$
690.0250	Sawing Concrete	49	LF	\$	\$
SPV.0090	Special 01. Concrete Curb & Gutter 24-Inch	290	LF	\$	\$
PROJECT TOTAL:				\$	

Note: All pages in this proposal shall be included as part of the bid package. Brown County reserves the right to reject any bids that do not include the proposal document in its entirety